

INOVUES, LLC

THERMAL PERFORMANCE TEST REPORT

SCOPE OF WORK

BASE UNIT

REPORT NUMBER

I6637.01-116-46 R0

TEST DATE

07/14/18

ISSUE DATE

07/26/18

RECORD RETENTION END DATE

07/14/23

PAGES


12

DOCUMENT CONTROL NUMBER

ATI 00025(c) (01/15/18)

RTTDS-R-AMER-Test-2822(c)

©2017 INTERTEK



TEST REPORT FOR INOVUES, LLC

Report No.: I6637.01-116-46 R0

Date: 07/26/18

REPORT ISSUED TO

INOVUES, LLC

2323 McCue Road

Houston, Texas 77056

SECTION 1

SCOPE

SERIES/MODEL: CW (Base Unit)

TYPE: Fixed

Intertek Building & Construction (Intertek B&C) was contracted by INOVUES, LLC to evaluate the thermal performance per AAMA 1503-09. The purpose of this testing was to evaluate the Condensation Resistance and Thermal Transmittance. Results obtained are tested values and were secured by using the designated test method. Testing was conducted at Intertek B&C test facility in York, Pennsylvania. This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

SECTION 2

SUMMARY OF TEST RESULTS

Condensation Resistance Factor - Frame (CRFf):	75
Condensation Resistance Factor - Glass (CRFg):	26
Thermal Transmittance (U):	1.07 Btu/hr·ft ² ·F

For INTERTEK B&C:

COMPLETED BY	Ryan P. Moser
TITLE	Senior Technician
SIGNATURE	
DATE	07/26/18

RPM:pan

REVIEWED BY	Shon W. Einsig
TITLE	Technician Team Leader, IIRC
SIGNATURE	
DATE	07/26/18

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.

TEST REPORT FOR INOVUES, LLC

Report No.: I6637.01-116-46 R0

Date: 07/26/18

SECTION 3

TEST SPECIMEN SUMMARY

SERIES/MODEL	CW (Base Unit)
TYPE	Fixed
OVERALL SIZE	53" x 77"
TEST SAMPLE SUBMITTED BY	Client

SECTION 4

TEST METHOD

The specimens were evaluated in accordance with the following:

AAMA 1503-09, Voluntary Test Method for Thermal Transmittance and Condensation Resistance of Windows, Doors and Glazed Wall Sections

SECTION 5

MATERIAL SOURCE/INSTALLATION

The test specimen was provided by the client. Representative samples of the test specimen will be retained by Intertek B&C for a minimum of five years from the test completion date.

Test Chamber Installation

The test sample was installed in a vertical orientation, the exterior of the specimen was exposed to the cold side.

SECTION 6

LIST OF OFFICIAL OBSERVERS

NAME	COMPANY
Joel T. Chronister	Intertek B&C
Ryan P. Moser	Intertek B&C
Shon W. Einsig	Intertek B&C

TEST REPORT FOR INOVUES, LLC

Report No.: I6637.01-116-46 R0

Date: 07/26/18

SECTION 7**TEST SAMPLE DESCRIPTION****Frame**

MATERIAL	AT (0.72"): Aluminum with Thermal Breaks - All Members		
SIZE	53" x 77"		
DAYLIGHT OPENING	48" x 72"	GLAZING METHOD	Exterior
EXTERIOR COLOR	Clear	EXTERIOR FINISH	Anodized
INTERIOR COLOR	Clear	INTERIOR FINISH	Anodized
CORNER JOINERY	Square Cut / Screws / Sealed		

Glazing Information

LAYER 1	1/4"	Tinted Glass
GAS FILL METHOD	N/A*	
DESICCANT	No	

Stated per Client/ManufacturerN/A Non-Applicable*

TEST REPORT FOR INOVUES, LLC

Report No.: I6637.01-116-46 R0

Date: 07/26/18

SECTION 7 (CONTINUED)

TEST SAMPLE DESCRIPTION (CONTINUED)

Weatherstripping

DESCRIPTION	QUANTITY	LOCATION
EPDM gasket	1 row	Interior and exterior glazing perimeter
EPDM thermal isolator	1 row	Frame at pressure plate center

Hardware

DESCRIPTION	QUANTITY	LOCATION
Aluminum pressure plate	4	Exterior frame perimeter
Aluminum face cover	4	Exterior frame perimeter
Aluminum adaptor	1 row	Interior glazing perimeter

Drainage

DRAINAGE METHOD	SIZE	QUANTITY	LOCATION
Diameter weephole	0.31"	2	Exterior sill face cover

TEST REPORT FOR INOVUES, LLC

Report No.: I6637.01-116-46 R0

Date: 07/26/18

SECTION 8**CONDENSATION RESISTANCE FACTOR**

1. Average Metering Room Air Temperature (th)	69.79 F
2. Average Cold Side Air Temperature (tc)	-0.38 F
3. Average of 14 Pre-Specified Frame Temperatures (FTp)	52.66 F
4. Average of 4 Roving Thermocouples (FTr)	43.98 F
5. Weighting Factor (W)	0.081
6. Weighted Frame Temperature (FT)	51.96 F
7. Average Glass Temperature (GT)	17.95 F
8. Condensation Resistance Factor – Frame (CRFf)	75
9. Condensation Resistance Factor – Glass (CRFg)	26

The CRF number was determined to be 26 (on the size as reported). When reviewing this test data, it should be noted that the glass temperature (GT) was colder than the frame temperature (FT) therefore controlling the CRF number. Refer to the 'CRF Report' page and the 'Thermocouple Location Diagram' page of this report.

SECTION 9**THERMAL TRANSMITTANCE**

1. Average Metering Room Air Temperature (th)	69.79 F
2. Average Cold Side Air Temperature (tc)	-0.38 F
3. Measured Static Pressure Difference Across Test Specimen	0.00" \pm 0.04" H ₂ O
4. Test Specimen Projected Area (As)	28.34 ft ²
5. Total Measured Input into Metering Box (Qtotal)	2303.92 Btu/hr
6. Total Correction	181.90 Btu/hr
7. Net Specimen Heat Loss (Qs)	2122.02 Btu/hr
8. Thermal Transmittance (U)	1.07 Btu/hr-ft ² -F

SECTION 10**TEST DURATION**

1. The environmental systems were started at 13:59 hours, 07/13/18.
2. The test parameters were considered stable for two consecutive four hour test periods from 23:55 hours, 07/13/18 to 07:55 hours, 07/14/18.
3. The thermal performance test results were derived from 03:55 hours, 07/14/18 to 07:55 hours, 07/14/18.

TEST REPORT FOR INOVUES, LLC

Report No.: I6637.01-116-46 R0

Date: 07/26/18

SECTION 11

TEMPERATURE AND CONDENSATION RESISTANCE CALCULATION

Time	05:55	06:25	06:55	07:25	07:55	Average
Pre-Specified Thermocouples - Frame						
1	46.70	46.66	46.70	46.67	46.72	46.69
2	47.08	47.05	47.04	47.05	47.04	47.05
3	47.84	47.81	47.83	47.86	47.85	47.84
4	57.21	57.21	57.20	57.23	57.26	57.22
5	55.79	55.80	55.81	55.82	55.79	55.80
6	54.99	55.01	55.00	55.00	55.02	55.00
7	58.17	58.14	58.17	58.16	58.20	58.17
8	55.79	55.81	55.79	55.80	55.81	55.80
9	55.48	55.46	55.45	55.45	55.49	55.47
10	54.10	54.09	54.12	54.13	54.11	54.11
11	52.73	52.72	52.71	52.72	52.72	52.72
12	52.38	52.38	52.39	52.40	52.38	52.39
13	49.47	49.45	49.45	49.47	49.48	49.47
14	49.49	49.50	49.51	49.51	49.48	49.50
FTp	52.66	52.65	52.65	52.66	52.67	52.66
Pre-Specified Thermocouples - Glass						
15	16.68	16.70	16.75	16.72	16.71	16.71
16	17.91	17.93	17.95	17.93	17.95	17.94
17	17.21	17.12	17.23	17.27	17.24	17.22
18	18.43	18.37	18.40	18.44	18.39	18.41
19	17.32	17.43	17.31	17.32	17.45	17.36
20	20.03	20.07	20.05	20.07	20.06	20.06
GT	17.93	17.94	17.95	17.96	17.96	17.95
Cold Point (Roving) Thermocouples						
21	43.40	43.40	43.40	43.40	43.40	43.40
22	43.80	43.80	43.80	43.80	43.80	43.80
23	44.10	44.10	44.10	44.10	44.10	44.10
24	44.60	44.60	44.60	44.60	44.60	44.60
FTr	43.98	43.98	43.98	43.98	43.98	43.98
W	0.081	0.081	0.081	0.081	0.081	0.081
FT	51.96	51.95	51.95	51.96	51.97	51.96
Warm Side - Room Ambient Air Temperature						
	69.78	69.77	69.81	69.80	69.81	69.79
Cold Side - Room Ambient Air Temperature						
	-0.46	-0.33	-0.35	-0.37	-0.36	-0.37
Condensation Resistance Factor						
CRFf	75	75	75	75	75	75
CRFg	26	26	26	26	26	26


TEST REPORT FOR INOVUES, LLC

Report No.: I6637.01-116-46 R0

Date: 07/26/18

SECTION 12

THERMOCOUPLE LOCATION DIAGRAM



COLD POINT LOCATIONS	
21	43.40
22	43.80
23	44.10
24	44.60

TEST REPORT FOR INOVUES, LLC

Report No.: I6637.01-116-46 R0

Date: 07/26/18

SECTION 13

GLAZING DEFLECTION

	FRAME
EDGE GAP WIDTH	N/A
ESTIMATED CENTER GAP WIDTH upon receipt of specimen in laboratory (after stabilization)	N/A
CENTER GAP WIDTH at laboratory ambient conditions on day of testing	N/A
CENTER GAP WIDTH at test conditions	N/A

Glass collapse determined using a digital glass and air space meter

The sample was inspected for the formation of frost or condensation, which may influence the surface temperature measurements. The sample showed no evidence of condensation/frost at the conclusion of the test.

Required annual calibrations for the Intertek B&C, 'thermal test chamber' (ICN 000001) in York, Pennsylvania were last conducted in May 2018 in accordance with Intertek B&C calibration procedure. A CTS Calibration verification was performed March 2018. A Metering Box Wall Transducer and Surround Panel Flanking Loss Characterization was performed April 2018.

ANSI/NCSL Z540-2-1997 type B uncertainty for this test was 1.66%.

Prior to testing the specimen was sealed with silicone on the interior side and checked for air infiltration per Section 9.3.4.

TEST REPORT FOR INOVUES, LLC

Report No.: I6637.01-116-46 R0

Date: 07/26/18

SECTION 14

DRAWINGS

Note: Dimensioned part drawings were unavailable at the time of testing; therefore, certain part details could not be confirmed by Intertek.

TEST REPORT FOR INOVUES, LLC

Report No.: I6637.01-116-46 R0

Date: 07/26/18

SECTION 15

REVISION LOG

REVISION #	DATE	PAGES	REVISION
.01 R0	07/26/18	N/A	Original Report Issue