

INOVUES, LLC

TEST REPORT

SCOPE OF WORK

ASTM E283, E331, MODIFIED E330 AND AAMA 501.1 R&D TESTING ON A CW AND CW+GS100LF, CURTAIN WALLS

REPORT NUMBER

I6575.01-109-44

TEST DATE(S)

07/18/18 - 07/20/18

ISSUE DATE

08/14/18

RECORD RETENTION END DATE


07/20/22

PAGES

17

DOCUMENT CONTROL NUMBER

ATI 00479 (07/24/17)
RT-R-AMER-Test-2805
© 2017 INTERTEK



TEST REPORT FOR INOVUES, LLC

Report No.: I6575.01-109-44

Date: 08/14/18

REPORT ISSUED TO

INOVUES, LLC

2323 McCue Road

Houston, Texas 77056

SECTION 1

SCOPE

Intertek Building & Construction (B&C) was contracted by Inovues, LLC to perform R&D testing in accordance with AAMA 501.1, ASTM E283, modified ASTM E330, ASTM E331, on their CW and CW+GS100LF, Curtain Walls. Results obtained are tested values and were secured by using the designated test method(s). Testing was conducted at Intertek B&C test facility in York, Pennsylvania.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

For INTERTEK B&C:

COMPLETED BY:	Ken R. Stough	REVIEWED BY:	Timothy J. McGill
TITLE:	Lead Technician – Product Testing	TITLE:	Manager – Product Testing
SIGNATURE:	 <small>Digitally Signed for: Ken R. Stough by Vicki L. McElwain</small>	SIGNATURE:	 <small>Digitally Signed by: Timothy J. McGill</small>
DATE:	08/14/18	DATE:	08/14/18

KRS:wnl

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.

TEST REPORT FOR INOVUES, LLC

Report No.: I6575.01-109-44

Date: 08/14/18

SECTION 2

SUMMARY OF TEST RESULTS

Test Specimen #1: CW

TITLE	RESULTS
Design Pressure	±2394 Pa (±50.00 psf)
Air Infiltration	<0.1 L/s/m ² (<0.01 cfm/ft ²)
Water Penetration Resistance Test Pressure	540 Pa (12.11 psf)
Dynamic Water Penetration Resistance Test Pressure	1436 Pa (30.0 psf)
Uniform Load Structural Test Pressure	±3591 Pa (±75.00 psf)

Test Specimen #2: CW+GS100LF

TITLE	RESULTS
Design Pressure	±2394 Pa (±50.00 psf)
Air Infiltration	0.1 L/s/m ² (0.01 cfm/ft ²)
Water Penetration Resistance Test Pressure	540 Pa (12.11 psf)
Dynamic Water Penetration Resistance Test Pressure	1436 Pa (30.0 psf)
Uniform Load Structural Test Pressure	±3591 Pa (±75.00 psf)

SECTION 3

TEST METHOD(S)

The specimens were evaluated in accordance with the following:

AAMA 501.1-17, *Standard Test Method for Water Penetration of Windows, Curtain Walls and Doors using Dynamic Pressure*

ASTM E283-04(2012), *Standard Test Method for Determining Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen*

Modified ASTM E330/E330M-14, *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*

ASTM E331-00(2016), *Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference*

TEST REPORT FOR INOVUES, LLC

Report No.: I6575.01-109-44

Date: 08/14/18

SECTION 4

MATERIAL SOURCE/INSTALLATION

Test specimen(s) were provided by the client. Representative samples of the test specimen(s) will be retained by Intertek B&C for a minimum of two years from the test completion date.

The specimen was installed into a Spruce-Pine-Fir wood buck. The rough opening allowed for a no shim space. The exterior perimeter of the window was sealed with silicone. Installation of the tested product was performed by the client.

LOCATION	ANCHOR DESCRIPTION	ANCHOR LOCATION
Head, sill and jambs	#14 x 3" hex head self-tapping screw	Located 4" from each end and midspan through the buck into the window frame

SECTION 5

EQUIPMENT

Control Panel: 003921, 005406

Weather Station: 63316

Spray Rack: 003956 C&D

Wolf: INT00003

SECTION 6

LIST OF OFFICIAL OBSERVERS

NAME	COMPANY
Anas Al Kassas	Inovues, LLC
Andrew P. Mehalick	Intertek B&C
Timothy J. McGill	Intertek B&C
Ken R. Stough	Intertek B&C

TEST REPORT FOR INOVUES, LLC

Report No.: I6575.01-109-44

Date: 08/14/18

SECTION 7

TEST SPECIMEN DESCRIPTION

Product Type: Curtain Wall and Curtain Wall with Inovues Glazing Shield

Series/Model: CW and CW+GS100LF

Product Size(s):

Test Specimens #1 and #2: CW and CW+GS100LF

OVERALL AREA:	WIDTH		HEIGHT	
	millimeters	inches	millimeters	inches
2.6 m ² (28.3 ft ²)				
Overall size	1346	53	1956	77

The following descriptions apply to all specimens.

Frame Construction:

MEMBER	MATERIAL	DESCRIPTION
Head, sill, and jambs	Aluminium	Extruded
Pressure plate	Aluminium	Extruded
Shear block	Aluminum	Extruded
Adaptor	Aluminum	Extruded
Cover cap	Aluminum	Extruded

	JOINERY TYPE	DETAIL
All corners	Square-cut, butted, and sealed	Sealed with butyl and secured with an extruded aluminum shear block. The shear block was secured to the jamb with two #12 x 2" pan head screws through the shear block into the jamb. The head and sill were secured to the shear block with two #12 x 7/8" flat head screws through the head / sill into the shear block.
Pressure plate	Square-cut and butted	Secured to the frame with #14 x 2" hex head self-drilling screws located 2" from each end and spaced 9 - 12" on center
Adaptor	Square-cut and butted	Snap-fit into the head, sill, and jambs
Cover cap	Square-cut and butted	Snap-fit onto the pressure plate

TEST REPORT FOR INOVUES, LLC

Report No.: I6575.01-109-44

Date: 08/14/18

Reinforcement: No reinforcement was utilized.

Weatherstripping: No weatherstripping was utilized.

Glazing: *No conclusions of any kind regarding the adequacy or inadequacy of the glass in any glazed test specimen(s) can be made.*

Test Specimen #1: CW

GLASS TYPE	GLAZING	GLAZING METHOD
Monolithic	1/4" annealed	Exterior glazed against an EPDM gasket and secured with a pressure plate with a EPDM gasket against the glass

Test Specimen #2: CW+GS100LF

GLASS TYPE	SPACER TYPE	INTERIOR LITE	EXTERIOR LITE	GLAZING METHOD
1-1/8" IG	Hybrid – aluminum profiles / extrusions between adhesives / sealants	1/4" annealed	1/8" annealed 0.060" PBV interlayer 1/8" annealed	Exterior glazed against an EPDM gasket and secured with a pressure plate with an EPDM gasket against the glass

Test Specimens #1 and #2: CW and CW+GS100LF

LOCATION	QUANTITY	DAYLIGHT OPENING		GLASS BITE
		millimeters	inches	
Fixed daylight opening	1	1219 x 1829	48 x 72	1/2"

Drainage:

DRAINAGE METHOD	SIZE	QUANTITY	LOCATION
Weephole	5/16" diameter	2	Located 2" from each end of the bottom rail under the cover cap through the pressure plate

Hardware: No hardware was utilized.

TEST REPORT FOR INOVUES, LLC

Report No.: I6575.01-109-44

Date: 08/14/18

**SECTION 8
TEST RESULTS**

The temperature range during testing was 26°C (79°F) to 29°C (85°F). The results are tabulated as follows:

Test Specimen #1: CW

TITLE OF TEST	RESULTS	ALLOWED	NOTE
Air Leakage, Infiltration per ASTM E283 at 75 Pa (1.57 psf)	<0.1 L/s/m ² (<0.01 cfm/ft ²)	Report only	1
Air Leakage, Infiltration per ASTM E283 at 300 Pa (6.27 psf)	<0.1 L/s/m ² (<0.01 cfm/ft ²)	Report only	1
Air Leakage, Exfiltration per ASTM E283 at 75 Pa (1.57 psf)	<0.1 L/s/m ² (<0.01 cfm/ft ²)	Report only	1
Air Leakage, Exfiltration per ASTM E283 at 300 Pa (6.27 psf)	<0.1 L/s/m ² (<0.01 cfm/ft ²)	Report only	1
Water Penetration, per ASTM E331 at 580 Pa (12.11 psf)	Pass	No leakage	
Dynamic Water Penetration per AAMA 501.1 at 1436 Pa (30.0 psf)	Visible water on sill	No leakage	5
Dynamic Water Penetration, Modified at 2107 Pa (44.0 psf)	Visible water on sill	No leakage	6
Dynamic Water Penetration, Modified at 2346 Pa (49.0 psf)	Visible water on sill	No leakage	7
Dynamic Water Penetration, Modified at 2490 Pa (52.0 psf)	Visible water on sill	No leakage	8
Uniform Load, per ASTM E330 +2394 Pa (+50.00 psf) -2394 Pa (-50.00 psf)	No damage	No damage	9, 10, 11
Air Leakage, Infiltration per ASTM E283 at 75 Pa (1.57 psf)	<0.1 L/s/m ² (<0.01 cfm/ft ²)	Report only	2

TEST REPORT FOR INOVUES, LLC

Report No.: I6575.01-109-44

Date: 08/14/18

Test Specimen #1: CW

TITLE OF TEST	RESULTS	ALLOWED	NOTE
Air Leakage, Infiltration per ASTM E283 at 300 Pa (6.27 psf)	<0.1 L/s/m ² (<0.01 cfm/ft ²)	Report only	2
Air Leakage, Exfiltration per ASTM E283 at 75 Pa (1.57 psf)	<0.1 L/s/m ² (<0.01 cfm/ft ²)	Report only	2
Air Leakage, Exfiltration per ASTM E283 at 300 Pa (6.27 psf)	<0.1 L/s/m ² (<0.01 cfm/ft ²)	Report only	2
Water Penetration, per ASTM E331 at 580 Pa (12.11 psf)	Pass	No leakage	
Uniform Load Structural, per ASTM E330 +3591 Pa (+75.00 psf) -3591 Pa (-75.00 psf)	No damage	No damage	9, 10

Test Specimen #2: CW+GS100LF

TITLE OF TEST	RESULTS	ALLOWED	NOTE
Air Leakage, Infiltration per ASTM E283 at 75 Pa (1.57 psf)	0.1 L/s/m ² (0.01 cfm/ft ²)	Report only	3
Air Leakage, Infiltration per ASTM E283 at 300 Pa (6.27 psf)	0.2 L/s/m ² (0.03 cfm/ft ²)	Report only	3
Air Leakage, Exfiltration per ASTM E283 at 75 Pa (1.57 psf)	<0.1 L/s/m ² (<0.01 cfm/ft ²)	Report only	3
Air Leakage, Exfiltration per ASTM E283 at 300 Pa (6.27 psf)	0.1 L/s/m ² (0.01 cfm/ft ²)	Report only	3
Water Penetration, per ASTM E331 at 580 Pa (12.11 psf)	Pass	No leakage	
Water Penetration, per AAMA 501.1 at 1436 Pa (30.0 psf)	No visible water	No leakage	5

TEST REPORT FOR INOVUES, LLC

Report No.: I6575.01-109-44

Date: 08/14/18

Test Specimen #2: CW+GS100LF

TITLE OF TEST	RESULTS	ALLOWED	NOTE
Water Penetration, per AAMA 501.1 at 2107 Pa (44.0 psf)	No visible water	No leakage	6
Water Penetration, per AAMA 501.1 at 2346 Pa (49.0 psf)	No visible water	No leakage	7
Water Penetration, per AAMA 501.1 at 2490 Pa (52.0 psf)	No visible water	No leakage	8
Uniform Load, per ASTM E330 +2400 Pa (+50.13 psf) -2400 Pa (-50.13 psf)	No damage	No damage	9, 10, 11
Air Leakage, Infiltration per ASTM E283 at 75 Pa (1.57 psf)	0.1 L/s/m ² (0.01 cfm/ft ²)	Report only	4
Air Leakage, Infiltration per ASTM E283 at 300 Pa (6.27 psf)	0.2 L/s/m ² (0.03 cfm/ft ²)	Report only	4
Air Leakage, Exfiltration per ASTM E283 at 75 Pa (1.57 psf)	0.1 L/s/m ² (0.01 cfm/ft ²)	Report only	4
Air Leakage, Exfiltration per ASTM E283 at 300 Pa (6.27 psf)	0.1 L/s/m ² (0.02 cfm/ft ²)	Report only	4
Water Penetration, per ASTM E331 at 580 Pa (12.11 psf)	Pass	No leakage	
Uniform Load Structural, per ASTM E330 +3591 Pa (+75.00 psf) -3591 Pa (-75.00 psf)	No damage	No damage	9, 10, 11

TEST REPORT FOR INOVUES, LLC

Report No.: I6575.01-109-44

Date: 08/14/18

General Note: *All testing was performed in accordance with the referenced standard(s).*

Note 1: Test Date 07/18/18 / Time: 3:50 PM

Note 2: Test Date 07/19/18 / Time: 3:00 PM

Note 3: Test Date 07/18/18 / Time: 4:12 PM

Note 4: Test Date 07/19/18 / Time: 4:45 PM

Note 5: Test duration of 15 minutes

Note 6: Test duration of 2 minutes

Note 7: Test duration of 30 seconds

Note 8: Test duration of 5 seconds

Note 9: *Loads were held for 10 seconds.*

Note 10: *Tape and film were not used to seal against air leakage during structural testing.*

Note 11: *No deflection on permanent set measures taken because of research and development testing.*

TEST REPORT FOR INOVUES, LLC


Report No.: I6575.01-109-44

Date: 08/14/18

SECTION 9

LOCATION OF AIR SEAL

The air seal between the test specimen and the test wall is detailed below. The seal is made of foam weatherstripping and is attached to the edge of the test specimen buck. The test specimen buck is placed against the test wall and clamped in place, compressing the weatherstripping and creating a seal.



TEST REPORT FOR INOVUES, LLC

Report No.: I6575.01-109-44

Date: 08/14/18

SECTION 10

PHOTOGRAPHS



Photo No. 1
Test Specimen #1 CW



Photo No. 2
Test Specimen #2 CW+GS100LF



Total Quality. Assured.

130 Derry Court
York, Pennsylvania 17406

Telephone: 717-764-7700
Facsimile: 717-764-4129
www.intertek.com/building


TEST REPORT FOR INOVUES, LLC

Report No.: I6575.01-109-44


Date: 08/14/18

SECTION 11 DRAWINGS


The test specimen drawings have been reviewed by Intertek B&C and are representative of the test specimen(s) reported herein. Test specimen construction was verified by Intertek B&C per the drawings included in this report. Any deviations are documented herein or on the drawings.



ELEVATION



SECTION



PLAN

NOTES:

PLAN, ELEVATION, AND SECTION ARE FOR SCHEMATIC PURPOSES

	Report #:	16575.01-109-44
	Date:	08/02/2018
	Verified by:	<i>Rev. L. Stuyf</i>

DRAWN BY: AA	SCALE 1:20	DIMENSIONS INCHES	SCH. DWG. NO. INO-002-01001	GLAZING SHIELD 1.0_PROTOTYPE 2_EPS
CHECKED BY:	DATE: 2018-04-24	CUSTOMER/REF.NO. ALLIANCE GLAZING TECHNOLOGIES	REVISION R1	



Total Quality. Assured.

130 Derry Court
York, Pennsylvania 17406

Telephone: 717-764-7700
Facsimile: 717-764-4129
www.intertek.com/building

TEST REPORT FOR INOVUES, LLC

Report No.: I6575.01-109-44

Date: 08/14/18

SECTION 12

REVISION LOG

REVISION #	DATE	PAGES	REVISION
0	08/14/18	N/A	Original Report Issue